



ADDENDUM NO. 3

PROJECT: RFT-2018-04 – Trail Construction for Giant’s Head Mountain Park Phase 1 & 2
DATE OF ADDENDUM: August 20, 2018

The Contract Documents for this work are revised as noted herein. All such revisions become a part of the work and shall be included in your tender. No consideration will be allowed for extras due to the tenderer not being familiar with this addendum.

1. REFERENCE: Supplementary Specifications: Geotechnical Engineering Input for MSE Retaining Wall Design

The following report is added to the Supplementary Specifications of the Contract Documents:

ADD: Geotechnical Engineering Input for MSE Retaining Wall Design (8 pages attached).

2. REFERENCE: Answers to Questions Received:

The following are answers to questions received up until the Inquiries Cut-off Date and Time:

Q1	In Appendix 1 – Schedule of Quantities and Prices, could you please clarify if line item 7.13 is a negative \$ amount to reflect that it is meant to remove a portion of line item 7.3?
A1	Confirmed – item 7.13 will be a negative \$ amount, as it is a reduction of the amount of trails to decommission in item 7.3. Tenderers shall enter the unit price for item 7.13 on the basis that it is a negative amount.
Q2	In Appendix 1 – Schedule of Quantities and Prices, what does “f.m.” mean?
A2	“f.m.” stands for exposed front face meters of all walls. The face meters is calculated by multiplying the height and length of the exposed front face of the walls.
Q3	Where is the optional retaining wall in the drawings?
A3	The optional gabion retaining walls are located at the Grind Crossing. See drawing L-1.0 and detail 4 / L-5.9. The board form optional price is for the premium between concrete walls with standard paperback forms and board forms.

END OF ADDENDUM NO. 3